

Mass DOT fast tracks bridge refurbishment with ELIMINATOR[®] system

ELIMINATOR[®] system waterproofs 14 bridges in 10 weekends on Fast 14 project



Project	Fast 14
Client	Massachusetts Department of Transportation
Contractor	JF White
Waterproofing Applicator	Chapman Waterproofing Inc.
GCP Solutions	ELIMINATOR [®] Bridge Deck Waterproofing system

Project

State agency accelerates bridge repair

The Fast 14 project was well named. In just ten weeks, the Massachusetts Department of Transportation (Mass DOT) replaced fourteen bridges on the busy I-93 near Boston.

In the summer of 2010, failure of a bridge deck on I-93 disrupted traffic for two days. Upon inspection on this and other structures, the Mass DOT found that the concrete decking and steel beams were failing on fourteen aging bridges. The repair work would normally have taken over four years, with drivers having to endure the resulting long-term traffic disruptions and consequential costs to the environment and the economy.

Instead, the Mass DOT decided to reduce the disruption using the recommended methods of the Federal Highways Accelerated Bridge Construction Program.

Challenge

Mass DOT gains fast curing, easy-to-apply waterproofing membrane

The Fast 14 project had demanding completion dates. To meet the project requirements, the Mass DOT needed a waterproofing system that could be applied with speed and ease, and would offer the durability needed for long-term protection of the bridges.

The Mass DOT chose the **ELIMINATOR**[®] system, based on unique **ESSELAC**[®] technology, to waterproof the 14 bridges, based on the product's proven track record of safeguarding U.S. bridges for more than 25 years. Developed by Stirling Lloyd (now GCP Applied Technologies), the **ELIMINATOR**[®] system is fast curing and highly durable to allow the waterproofing membrane to be overcoated in 40 minutes. This made it the best choice for this fast-track project.



Solution



ELIMINATOR[®] saves time and money

After the Friday evening rush hour, crews changed the traffic flow on I-93, dismantled the bridge, brought in new prefabricated concrete bridge panels, joined them together with rapid setting concrete diaphragms and applied temporary road markings. The new bridge was opened in time for the Monday morning rush hour, minimizing disruption to local commuters. On a following weekend, the waterproofing was installed.

The deck was shotblasted to provide a clean surface, followed by the application of the PAR1 primer. The ELIMINATOR[®] membrane was then spray applied in two contrasting coats, which enabled the applicator to check the correct and complete coverage of the membrane, even when applied at night.

To provide a high friction, skid-reducing surface, aggregate was broadcast into the second coat of the ELIMINATOR[®] membrane to provide a temporarily trafficable wearing surface. The surface was later brushed off and a proprietary bond coat was applied before the application of the asphalt wearing course.

The ELIMINATOR[®] system contributed significantly to the time and cost savings on this project.

Blue360SM Total Business Advantage.

The power of GCP products, performance and people

North America customer service: 1-877-4AD-MIX (1-877-423-6491)

Ce document est à jour seulement à la date de la dernière mise à jour indiquée ci-dessous et n'est valide que pour une utilisation au Canada. Il est important que vous consultiez toujours les informations actuellement disponibles sur l'URL ci-dessous pour fournir les informations les plus récentes sur le produit au moment de l'utilisation. Des documents supplémentaires tels que les manuels de l'entrepreneur, les bulletins techniques, les dessins détaillés et les recommandations détaillées ainsi que d'autres documents pertinents sont également disponibles sur www.ca.gcpat.com. Les informations trouvées sur d'autres sites Web ne doivent pas être utilisées, car elles peuvent ne pas être à jour ou applicables aux conditions de votre site et nous déclinons toute responsabilité quant à leur contenu. S'il y a des conflits ou si vous avez besoin de plus d'informations, veuillez contacter le service client de GCP.

Last Updated: 2018-12-12

ca.gcpat.com/about/project-profiles/mass-dot-fast-tracks-bridge-refurbishment-eliminator-system