

CalPortland Company Uses GCP Concrete Admixtures for Ambitious Continuous Pour



| | |
|---------------------------------|---|
| Project | Bay State Grain Silos |
| Client | Bay State Milling |
| Ready-mix producer | CalPortland Company |
| Concrete contractor | McCormick Construction Company |
| GCP solutions | RECOVER [®] , WRDA [®] 64, and DARACEM [®] 55 admixtures |
| Concrete mix and specifications | 4,500 psi |
| Volume | 6,000+ yards of concrete |

The Project

4,500

PSI

6,000+

Yards of Concrete

McCormick Construction was hired to construct 24 slipform concrete grain silos that would each rise 140 feet in the air. The creation of the silos was set to be a continuous pour spanning nine straight days, 24 hours a day. For this type of complex construction, McCormick Construction used an intricate slip forming process.

For the ready-mix concrete, McCormick awarded the project to CalPortland Company, the largest cement and construction material producer on the west coast. “We worked with CalPortland on a project in Washington years ago, and their staff and attention to detail were top notch,” said McCormick Construction Chief Operating Officer Steve Swanson. “They are all about making sure customers get what they want.”

The Challenge

The sheer size of the slip footprint and the small (21') diameter of the silos made it critical to select the right mix design. "We needed concrete that would flow easily through the congested rebar and would perform well in extreme temperatures," said Swanson.

"The biggest challenge of the project was pouring concrete in ambient conditions exceeding 100° F, which required pre-trials on set times throughout the day," explained CalPortland Company Director of Quality Control in Arizona Lauro Rivas, P.E. "We needed large quantities of chilled water and ice for temperature control measures. Having pre-conditioned/tested aggregates was also key for cooling the coarse aggregate and maintaining SSD moisture."

For this intensive project, the concrete had to set fast enough to support the concrete above it, and also needed to remain pumpable. "We pour concrete at sites across the U.S., and each one requires its own 'brew,'" said Swanson. "For this project, we performed numerous test pours with CalPortland and were pleased to get the mix the right way we wanted it."

The process required a fair bit of mix optimization, as well as stringent quality control to maintain the mix. CalPortland performed laboratory and field trials to test for optimum set time, slump retention, and temperature control. Throughout concrete production, a CalPortland QC technician worked at the plant and at the jobsite at all times, checking and adjusting concrete loads to maintain consistency.

<https://player.vimeo.com/video/448842128>

Construction of Bay State Grain Silos, video courtesy of McCormick Construction.

"We needed concrete that would flow easily through the congested rebar and would perform well in extreme temperatures,"

Steve Swanson, McCormick Construction Chief Operating Officer Steve Swanson.

The Solution

CalPortland chose RECOVER® hydration stabilizer, WRDA®64 water reducing admixture, and DARACEM®55 mid-range water-reducing admixture for the project. "GCP admixtures all worked together with the appropriate dosages to improve slump retention and set time extension, which were optimal for hot weather conditions," Rivas said.

- The RECOVER® admixture is a chemical compound designed to stabilize the hydration of Portland cement concretes.
- The WRDA® admixture improves concrete performance, making it more workable and easy to place and finish. It is often chosen for mix designs requiring high compressive and flexural strength.
- DARACEM® 55 water-reducing admixture produces concrete with low water content and improved placement properties. It also imparts a "slickness" to the surface of the concrete, making it a good choice for slip form work.

"The biggest challenge of the project was pouring concrete in ambient conditions exceeding 100° F, which required pre-trials on set times throughout the day,"

CalPortland Company Director of Quality Control in Arizona Lauro Rivas, P.E.

The Results

"It takes a huge team effort to maintain consistency when you supply a 24-hour, eight-nine day continuous pour," said CalPortland's Phoenix Ready-mix Operations Manager Paul Marsh. "Our batch plant operators, drivers, and quality control team did a great job working together to ensure a successful finish."

"It was a successful pour and our customer was pleased with the consistency and the mix performance," Rivas said. "With GCP admixtures, I felt like we had control of the set time in the mix," Swanson said. "The results were stellar."

"GCP admixtures all worked together with the appropriate dosages to improve slump retention and set time extension, which were optimal for hot weather conditions,"

CalPortland Company Director of Quality Control in Arizona Lauro Rivas, P.E.

ca.gcpat.com | North America customer service: 1-877-4AD-MIX (1-877-423-6491)

GCP Applied Technologies Inc., 2325 Lakeview Parkway, Suite 450, Alpharetta, GA 30009, USA

GCP Canada, Inc., 294 Clements Road, West, Ajax, Ontario, Canada L1S 3C6.

This document is only current as of the last updated date stated below and is valid only for use in the Canada. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on www.gcpat.com. Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.

Last Updated: 2023-06-29

ca.gcpat.com/about/project-profiles/calportland-company-uses-gcp-concrete-admixtures-ambitious-continuous-pour